

THE WORLD SPA APARTMENT OWNERS ASSOCIATION, SEC. 30/41, GURUGRAM						
Bill of Quantity For Lift Shaft Plaster Work in Tower A2 & B3						
Sr.	Work DESCRIPTION	UoM	Qty.	Rate	AMOUNT	
1	Dismantling and demolishing of Existing loose Plaster on lift shaft wall's in all respect , Manually as per requirement at all level and heights including scaffolding if required and complete as per instruction of Site-Incharge.	SQFT	5000			
2	Providing and applying of Ready -mix Motar Plaster Make (Ultratech) up to 12 mm to 15 mm thick Plaster or finished in all Respect at all Level and Hights Including scaffolding if required and Complete as per instrunction of site- incharge.	SQFT	5000			
3	Malba shifting work in 2.5cum per Trip By tractor & trolly	Nos	3			
		TOTAL				
		Add SGST @ 9%				
		Add CGST @ 9%				
		Grand Total				
Note :-						
Gaurav 11/04/25 Civil Engg		Vinod 11.04.2025 Technical Manager		Manoj 11.4.2025 Estate Head		BOM BOM
Abante SMEs 11/04/25		Infra Committee Member 11/04/25				