

The World Spa Apartment Owners Association

Sector -30/41 Gurugram

BOQ For Cassette AC units for Towers A-5&B-3

S.No	Description	UOM	Quantity	Rate of supply	Rate of erection	Ammont of supply	Ammont of Erection
	Higher Side						
1	Supply 4.0TR 3 star Cassette AC, Make- Daikin, Non Invertor complete set indoor and out door unit (THREE PHASE)	Nos	2				
	Low Side - Installation work						
2	Dismantling of existing Cassette units and copper pipe (Indoor to out door)	Nos	2				
3	Installation of 4 TR indoor and out door units with required fittings and supports, Nitrogen hold test minimum 48 hrs.	Job	2				
4	Supply and installation 5/8 Dia Refrigerant copperpipe , make Malaysia with 9mm insulation	RMT	8				
5	3/8 DIA Refrigerant copper pipe , make Malaysia with 9mm insulation	RMT	8				
6	Supply and installation of 40mm drain Pipe with 9mm insulation	RMT	10				
7	Supply and installation of copper conductor Control cabling 8CoreX 2.5mm Make - Finolex, Havells,	RMT	10				
8	Supply and installation of outdoor unit painted stand 40x40x5mm or as per company recommendation	Nos	2				
9	Loading unloading and freight	Job	1				

** Quantity may vary during execution of site

** Final billing of low sidework will be proceed as per actual measurement

Prepared by
Udairaj Singh
Manager-Technical

Received By
Harpreet Singh
Estate-Head
08-05-2025

Authorized BOM