

The World Spa Apartment Owners Association

Sector -30/41 Gurugram

BOQ For Ductable AC units for West Club

S.No	Description	UOM	Quantity	Rate of supply	Rate of Erection
Higher Side Work					
1	Supply of 1 1 TR Ductable single circuit AC, Make- Daikin, non Inverter three phase complete indoor and out door.	Nos	1		
Low Side - Installation work					
2	Dismantling of existing units and copper pipe (Indoor to outdoor)	Nos	1		
3	Installation of 1 1 TR indoor and out door units with required fittings , supports and Nitrogen hold minimum 48 hrs.	Job	1		
4	Supply and installation of 29 mm DIA Refrigerant copper heavy pipe with 19mm insulation (1 1/8) and required fittings,supports ,make Mandev, or Daikin approved	Rmtr	20		
5	Supply and installation of 15.9mm DIA Refrigerant copper heavy pipe, with 19mm/13mm insulation (5/8) and required fitting and supports , Make Mandev ,Or Daikin approved.	Rmtr	20		
6	Supply and installation of 40mm Drain Pipe with insulation 9 mm and required fittings, supports	Rmtr	3		
7	Supply and installation of Controlling copper conductor flexible cabling 8 Core X 2.5mm, with PVC conduit and required fittings and supports ,Make - Finolex, Havells	Rmtr	25		
8	Out door unit painted Stand 40x40x5mm or as per company recommendation if required	Nos	1		
9	Loading , unloading and freight	Job	1		
10	Canvas Connection as per indoor size	Nos	1		
11	9mm Acoustic Insulation if required	Sqm	7.5		
12	Duct insulation nitrile 9mm if required	Sqm	7.5		
13	Supply and installation GI ducting/ plenum-22G, make Jindal, If Required modification as per indoor size	Sqm	7.5		
14	Dismantling of existing GI Ducting If Required	sqm	7.5		

** Quantity may be vary during execution the work

** Final bill Low side work will be proceeded as per actual measurement

Prepared By
Udairaj Singh
Manager-Technical

Recommended By
Harpreet Singh
Estate-Head

Authorized BOM