

**The World Spa Owner Association Sec 30/41 Gurgaon**  
**BOQ FOR Main Gate/Nursary side Fencing Work**

**Fencing Work :-**

S. NO.	ITEM DESCRIPTION	U.O.M.	QTY.	UNIT PRICE	Amount	Remark
1	Dismantling steel work in built up sections in angles, flats and channels including welding etc. ( As Per Requirement ) including dismembering and stacking within 50 meters lead.	Kg	1500			
2	Providing & Installation Work of Angle , Jail For Fencing work ( Specification Of Angle 40*40*5, Jail 1"1" Thickness of wire 2 mm)	Kg	1700			
3	Providing and laying in position ready mixed or site batched design mix cement concrete for M20 (Ratio 1:2:4 ) ; using coarse aggregate and fine aggregate derived from natural sources, URP 301 /LW+ Ordinary ortland /Portland Slag cement, admixtures in recommended portions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength;concrete to site of laying, curing, carriage for all leads; as per direction of the engineer-in-charge ( Footing Size - 0.45*0.45*0.3)	Nos	If Required			
4	Painting with synthetic enamel Primer & paint of approved brand ( Berger ) and manufacture to give an even shade ( Bus Green ) : Two or more coats on new work	Sqft	2200			
<b>Total Amount</b>						

**Note :- 1. Final Payment As Per Actual Measurement**

**2. Electricity supply provided by Client without any Cost.**

Mr Gaurav Dagar  
Sr.Executive Civil

Mr Udairaj Singh  
Technical Manager

Mr Harpreet Singh  
Estate Head

Mr J.B Ruhil  
SME AIMSPCL

Mr Santosh Agarwal  
Infra Committee

Ms Myrelle Machado  
Aouthrised BOM

*for monthly*  
*19/08/2025*

*Signature*  
*Vinod Singh*

*Signature*  
*myrelle*