

The World Spa Sec - 30/41 Gurgaon

BOQ for Sports Court's PCC Work

SI no		Work Description		UoM	Qty	Rate
1		Dismantling of Tiles works to reach the mother slab and removing of filling material, Disposal of malwa and stacking of serviceable material near by location.		Sqm	162	
2		Cleaning of RCC surface to remove dust, already applied coating by grinding, loose particles, etc with compressed air or any other suitable technique depending on site conditions, grinding any sharp edges.		Sqm	162	
3		Waterproofing membrane: Supplying and applying single component high tensile, high solid, moisture cured polyurthane elastomeric liquid membrane HS Elastoseal 1K for waterproofing in two coats by brush, roller or airties spray for maintaining thickness of 1mm having Elongation > 700% & Tensile strength > 2Mpa (ASTM D 412), Crack bridging up to 1.5 mm (ASTM C836). The system includes one so coat of HS Elastoseal primer @ 8-10 sqm/ltr on dry prepared surface complete as per manufacturers specification. (Make Fosroc)		Sqm	162	
4		Providing and laying 200 GSM Geo textile layer over the waterproofing coating.		Sqm	162	
5		Providing and Laying of Screed : Laying protective screed Plain Cement Contete of M20 grade (Ratio 1:1.5:3) with 50mm thick and adding of waterproof chemical 200ml (Urp 301/Lw+) per 50kg bag or recomanded by SC manufacturer, curing for 7 days etc. complete. (by Pumping system and RMC)		Cum	8	
6		Disposal of Mabla out of World Spa using Tractor capacity 2.5 CUM per trip Trip		Nos	4	
				Amount		
				Gst 18%		
				Total Amount		
Note :- 1. Final Bill As per Actual Measurement						
2. PCC Level/As zero Level its for sports court's.						
Mr Gaurav Dagar		Mr Udayraj Singh		Mr Harpreet Singh		
Sr Civil Executive		Tech. Manager		Estate Head		
Mr. J.B Ruhil		Mr. Santosh Agarwal		Ms. Myrell Machado		
SME AIMSPL		Infra Committe		Aouthrsied BOM		


Virender Singh