

The World Spa Sec - 30/41 Gurugram

BOQ for Compost plant area PCC & Fabrication Work

| Sl no | Work Description | UoM | Qty | Rate |
|-------|--|--------------|-----|------|
| 1 | a. Supplying & Erection of MS columns (40 mm x 2.8thickness) MS Pipe Including Welding and fixing with Chemical Fastner 200mm long (fastner Make Hilti) in floor etc as per existing design . b. Supplying and erection of MS beams/purlins (40*40*2.8 mm) rectangular Including Welding . | Kg | 300 | |
| 2 | Supplying and Installation work of Metro sheet on top of Shade (0.5 mm Thick) with metro Screw with GI charcoal washer and Fabrication Work | Sqft | 880 | |
| 3 | Providing and Laying of Screed : Laying protective screed Plain Cement Concrete of M20 grade (Ratio 1:1.5:3) with 150mm thick and adding of waterproof chemical 200ml (Urp 301/Lw+) per 50kg bag or recommended by SC manufacturer, curing for 7 days etc. complete.(By Pumping & RMC) | Cu m | 8.5 | |
| 4 | Providing and Laying of Screed : Laying protective screed Plain Cement Concrete of M20 grade (Ratio 1:1.5:3) with 75mm thick and adding of waterproof chemical 200ml (Urp 301/Lw+) per 50kg bag or recommended by SC manufacturer, curing for 7 days etc. complete.(By Pumping & RMC) | Cu m | 12 | |
| | | Amount | | |
| | | Gst 18% | | |
| | | Total Amount | | |

Note :-

1. Final Bill As per Actual Measurement

2. Work with Pumping & RMC

Gaurav
14/11/25
Mr Gaurav Dagar
(Sr Civil Executive)

Udairaj
Mr Udairaj Singh
(Tech. Manager)

Harpreet
Mr Harpreet Singh
(Estate Head)

Mr. J.B Ruhil
(Civil Head AIMSPL)

Mr. Santosh Agarwal
(Infra Committee - TWSAOA)

Ms. Myrelle Machado
(Authorised BOM)

for monthly
14/11/2025