


The World Spa Owner Association Sec 30/41 Gurgaon						
Construction of a Gazebo of size 4.29 x 3.75 meters as per Existing Drawing						
S. NO.	Gazebo work :-	U.O.M.	QTY.	Rate	Amount	Remark
1	ITEM DESCRIPTION Four pillars of size 150x150mm Malaysian Sal wood shall be resting on CC footing size 600x600x600mm. Four J bolts 450mm shall be producing out of the footing to fix 300x300x8mm thick mat finish SS plate. 150x150x3mm mat finish S.S sleeve shall be inserted to the vertical wooden posts by making grooves in the posts, and this sleeve will be welded to 8mm thick SS plate for rigidity. The sleeve and wooden vertical post shall be held together by two bolts passing through the wood. Top shall be covered with safety glass minimum 10mm thick fixed on wooden Malaysian hard wood purlins of size 100mmx75mm. All wooden shall be finished with oil paint.	LS				
2	Earth work in Excavation by manual mean of foundation & surface area, including dressing of sides and ramming of bottoms, for all lift work including getting out the excavated soil and disposal of surplus excavated soil, within a lead of 50m. Footing Size (600mm*600mm*600mm)	cum	0.964			
3	Providing and laying M25 Grade cement concrete in foundation shall be from natural source:3 graded stone aggregate 20mm nominal size driven from the natural source). (footing size : 600mm*600mm*600mm)	cum	0.964			
4	Supplying, stacking and Sepreading 50 mm thick Stone Sand for laying of PCC on Floor Area.	cum	1.000			
5	Providing and laying in site batched design mix cement concrete for plain cement concrete work using coarse aggregate and fine aggregate shall be from natural sources. Concrete of M15 grade with minimum cement content of 240kg/cu m.(Thickness Of PCC 100mm)	cum	1.6			
6	Providing & Laying of the 25mm thick cement mortar bedding for laying of vitrified tiles (200mm*1200 mm) with jointing.-Kajaria Make	sqm	16.1			
	Total Amount					
	Discount					
	After Discount					
	Gst 18%					
	Amount With GST					
	Vendor Status					
Note :- 1. Electricity supply provided by Client without any Cost. 2. All work area shall be covered by green Net.						
 Gaurav Dagar Sr. Civil Executive		 Kapil Vats 21/8/2025 Project Manager-EO		 Harpreet Singh Estate Head		
 Sarfosh Agarwal Infra Committee-TWSAOA		 Myrelle Machado Authorized BOM				