

The World Spa Owner Association Sec 30/41 Gurgaon

BOQ For MPH Flooring Vinyl Sheet Work

S. NO.	ITEM DESCRIPTION	U.O.M.	QTY.	UNIT PRICE	Amount	Remark
1	Supply and installation 4.5 mm thick Armstrong Anti skid vinyl Flooring as per approved colour and Shade Maple BG-6819 manufactured in accordance with ISO 10581 and installed with Polyflor recommended adhesive. Includes all cutting work, installation work with the adhesive. Joints must be butted, U-shape grooved and heat welded using Polyflor's matching welding rod.	Sqft	1280			
2	Coving and Welding of 4.5 mm thick Armstrong vinyl sheet in approved Colour and shade Maple BG-6819	Rft	350			
Total Amount						

Note :-


1. Final Payment As Per Actual Measurement


12/8/25
Gaurav Dagar
Sr.Executive Civil


12/8/25
Kapil Vats
Project Manager


12/8/25
Udairaj Singh
Technical Manager


12/8/2025
Harpreet Singh
Estate Head


J.B. Ruhil
Civil Head AIMSPL


Santosh Agarwal
Infra Committee

Myrelle Machado
Authorised BOM